

Deactivated Nuclear Power Plant Program

Presenter

Mr. Gregory Komp

Director, Army Radiation Safety

Mr. Hans Honerlah

Baltimore District, US Army Corps of Engineers

10 July 2014



®

US Army Corps of Engineers
BUILDING STRONG®



Agenda

- History
- All Hazards Assessments (AHA)
- Baltimore Support to Army Reactors
- STURGIS



Historical DoD Reactor Uses

- Atomic weapons production
- Naval Nuclear Propulsion
- Army Nuclear Power Program
- DoD research missions



U.S. Army Nuclear Power Program

- 1952 DoD study to determine the feasibility of developing reactor plants to serve military power needs on land
- Joint program between DoD and the Atomic Energy Commission
- Each service participated in the Army managed program



U.S. Army Nuclear Power Program

- DOD exempted from the Atomic Energy Act (AEA) –1954
 - Section 91(b) – Military Application of Atomic Energy (Authority)
 - Section 110(b) – Atomic Energy Licenses (Exclusions)



U.S. Army Nuclear Power Program

- Army implements its authority in AR 50-7, Army Reactor Program
 - Army utilizes a permitting process for all phases of operation to include decommissioning
 - Whenever feasible, the Army uses NRC procedures to manage exposure and contamination.
- The NRC concurred in a similar situation that the Army Reactor Program material was not under NRC authority for licensing or disposal.



U.S. Army Nuclear Power Program

- A total of 9 reactors were built and operated between 1957 and 1977
- 6 DoD Reactors (4 Army, 1 AF, 1 Navy)
- 3 prototype reactors developed at the National Reactor Testing Station in Idaho
- Benefited the concurrent development of commercial nuclear power



SM-1 During Operation at Fort Belvoir, VA




SL-1 During Operation at NRTS



INEEL Photo



GCRC During Operation at NRTS




ML-1 During Operation at NRTS



PM-2A During Construction at Camp Century, Greenland




PM-1 During Operation at Sundance, WY



STRONG®

PM-1 Site After Decommissioning at Sundance, WY



PM-3A During Operation at McMurdo Station, Antarctica




After PM-3A Decommissioning at McMurdo Station, Antarctica



Photo from southpolestation.com



SM-1A During Operation at Fort Greely, AK



MH-1A During Testing at Fort Belvoir, VA



Army Power Reactor Deactivation and Safe Storage

- Reactor fuel and control rods removed and returned to AEC/DOE
- Facility areas decontaminated or restricted from access
- Primary systems grouted or sealed, access doors welded shut
- Planned 50 years storage prior to “free release” and dismantlement



Army Reactor Program

- The USACE currently holds permits issued by the Army Reactor Office (ARO) for three deactivated nuclear reactors.
 - SM-1, Fort Belvoir, Virginia (1957 to 1973)
 - SM-1A, Fort Greely, Alaska (1962 to 1973)
 - MH-1A, *Sturgis* Barge, James River Reserve Fleet, Fort Eustis, Virginia (1966 to 1978)

- The ARO also has permits issued for two deactivated research reactors.
 - APRF, APG, MD (1967 to 2004)
 - DORF, Forest Glen Annex, MD (1961 to 1977)



All Hazards Assessment

- Phase I – Historical Site Assessment to prepare data quality objectives and site conceptual model
- Phase II – conduct radiological and non-radiological sampling and analysis, disposal alternatives evaluation, and cost estimates for the decommissioning
- Phase III – design and execution of the decommissioning plan
- Phase IV – final status surveys and permit termination



Baltimore District

All Hazards Assessment Status

- **STURGIS AHA Phase III initiated**
 - Decommissioning Permit Issued
 - Contract for D&D Awarded
 - FY14-FY17
- **SM-1 AHA Phase II completed**
 - Updating Reports
- **SM-1A AHA Phase II completed**
 - Updating Reports
- **APRF AHA Phase IV in-progress**
- **DORF AHA Phase IV in-progress**




Army Regulation 50-7

- AR 50-7 Requirements for Decommissioning Permit
 - Approved NEPA Decision Document
 - Completed Historical Site Assessment
 - MOA with SHPO in accordance with the NHPA
 - Coordination with other stakeholders and regulators
 - Classification of areas to be decommissioned
 - Health and Safety framework
 - Final Decommissioning Plan, Waste Management Plan, and Disposal Plan



STURGIS Organization Chart



USACE Contractor Team

- Contract Awarded for \$34.6M in March 2014
- Period of Performance 48 months

	CB&I <i>Prime Contractor</i>
Project Management Quality Assurance Safety and Health Radiological Program Project Controls	Contract Management Procurement Decommissioning Dismantlement Engineering
	EnergySolutions
Waste Management Radiological Controls Waste Certifications	Waste Transport Waste Disposal Regulatory Support
	Malin International
Towing Plan Naval Architect Pierside Operations	Decommissioning Facility Shipyard Labor Drydock (Submersible Barge)
	EMR
Ship Breaking, Recycling, and Vessel Disposal	

STUR_103_5

Primary Objectives

- Relocate the STURGIS to the selected decommissioning site;
- The contractor will prepare plans that will support the decommissioning of the STURGIS in accordance with the contract, the ARO Decommissioning Permit, and other applicable requirements;




Primary Objectives

- Decommission/dispose of materials in accordance with final plans, decommissioning permits, and relevant Federal and State requirements; and
- Adherence to NRC and Army, as well as other Federal standards and guidance where relevant as required by the Army Reactor Office and USACE.



STURGIS MH-1A



STUR-PAL_300_2

STURGIS D&D Plans

- Towing/Mooring/Stability Plan
- Decommissioning Work Plan
- Quality Assurance Project Plan
- Hazardous Material Work and Abatement Plan
- Pre-Demolition Survey Plan
- Material Categorization, Survey, and Release Plan
- Final Status Survey Plan
- Waste Management Plan (site-specific)
- Waste Transportation and Disposal Plan



STURGIS D&D Plans

- Accident Prevention Plan
 - Site Health and Safety Plan
 - Air Monitoring Plan
 - Radiation Protection Plan
 - Lead Compliance Plan
 - Asbestos Hazard Control Plan
 - Critical Lift Plan
 - Emergency Response Plan




Technical Approach

- Inspection and Relocation of STURGIS to Galveston for decommissioning
- Baseline Survey at Shipyard
- Preparation of STURGIS for D&D
- Decommissioning STURGIS' radiological and hazardous materials including packaging, certification, transport and disposal



Galveston Site Overview

Malin International Shipyard



Technical Approach

- Survey and release of the balance of the vessel hull and work area
- Transport of the semi-submersible barge holding STURGIS to EMR in Brownsville, Texas for breaking and recycling
- Project closeout and reporting



